IV B.Tech - I Semester –Regular / Supplementary Examinations JANUARY - 2022

FINITE ELEMENT METHODS (MECHANICAL ENGINEERING)

Duration: 3 hours

Max. Marks: 70

PART – A

Answer *all* the questions. All questions carry equal marks 11x 2 = 22 M

1.

- a) Define Discrete system with an example.
- b) What do you mean by boundary conditions?
- c) Describe the characteristics of shape functions.
- d) List various forces acting on a 1D linear Bar element.
- e) Distinguish between local coordinate system and global coordinate system.
- f) Write down the finite element equation for a beam element.
- g) Define Plane stress and Plane Strain conditions.
- h) Write down the strain displacement matrix for 4 noded quadrilateral element.
- i) What are the thermal boundary conditions for a composite wall?
- j) Write down the Stress-Strain relationship matrix for an axi-symmetric triangular element.
- k) List some of the software packages available for Finite Element Methods.

PART - B

Answer any *THREE* questions. All questions carry equal marks. $3 \ge 16 = 48 \text{ M}$

- 2. Explain the Raleigh Ritz method of functional approximation with the help of an example in detail.
 16 M
- 3. Consider the bar as shown in Figure 1. Determine the nodal displacements, stresses induced in the elements and Reaction forces at the supports.16 M





Figure 1

4. For beam shown in Figure 2, **compute** the deflection at the element nodes. The modulus of elasticity is E = 200 GPa and the cross section is as shown in figure. Use the finite element method with minimum number of elements. 16 M



- 5. Derive the element stiffness matrix for a 3 nodded triangular element (CST) and also derive the equivalent nodal force matrix for Traction force and Body force terms.16 M
- 6. A composite wall consists of 3 materials shown in Figure 3 below. The outer temperature is $T_0 = 20$ °C. Convection heat transfer takes place on the inner surface of the wall with T_{∞} =800°C and h = 25 W/m² °C. Determine the temperature distribution in the wall. 16 M




Figure 3